BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No. RRND/EE/Tend/12/2020-21, Date: 22.02.2021

Indet No: BBMP/2020-21/RD/WORK_INDENT47076

SCHEDULE -B

Name of Work: Providing Asphalt works at selected reaches in ward no 17 Phase-02

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	428.76	Removing & Refixing stone slabs of drains and pointing in C.M (1:3)	Sqm	117.00	Rupees One Hundred Seventeen Only
2	247.92	Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per	Cum	247.00	Rupees Two Hundred Forty Seven Only
3	1.65	Plain cement concrete 1:3:6 mix with crushed stone aggregate 40 m nominal size mechanically mixed, placed in foundation and compacted by vibration including curing complete as per specifications MORTH Specification No	Cum	4701.00	Rupees Four Thousand Seven Hundred One Only
4	5.64	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specifications.Wall & bottom thickness 15cm	Cum	7420.00	Rupees Seven Thousand Four Hundred Twen Only
5	0.45	Providing T.M.T. steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per disign (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification.s	Tonne	84114.00	Rupees Eighty Four Thousand One Hundred Fourteen Only
6	571.68	Providing and constructing precast concrete solid blocks with compressive strength not less than 3.5 Newton per sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x15x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.-do with solid concrete blocks of s	Sqm	1048.00	Rupees One Thousand Forty Eight Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

7	285.84	Providing ruled pointing to coursed stone masonry with cement mortar, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, HOM curing complete as per specifications.– do – cement mortar 1:3(	Sqm	158.00	Rupees One Hundred Fifty Eight Only
8	42.88	Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing omplete as per specifications.	Cum	6028.00	Rupees Six Thousand Twenty Eight Only
9	428.76	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete.- do - 10 cms thick	Sqm	1015.00	Rupees One Thousand Fifteen Only
10	428.76	Providing two line dressing to granite stone slab / granite stone masonry as per specifications.	Sqm	1663.00	Rupees One Thousand Six Hundred Sixty Three Only
11	2574.00	Providing chamfering edges to stone slab 2.5 cms. Wide as per specifications. (only chamfered length shall be recorded)	Sqm	65.00	Rupees Sixty Five Only
12	12.00	Providing & laying precast drain cover slab of 250 mm thickness in CM 1:3 including cost of all materials, labour, curing, transportation, loading, unloading etc, complete as per the directions of the Engineer In Charge.(1.2 x 0.60 x 0.25) (Approved Data rate)	Sqm	5418.00	Rupees Five Thousand Four Hundred Eighteen Only
13	1588.00	Providing and fixing pre cast solid concrete kerb stones of size 450x150x500 mm made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting ete.,	Nos	480.00	Rupees Four Hundred Eighty Only
14	285.84	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.	Sqm	89.00	Rupees Eighty Nine Only
15	643.14	. Excavation for roadwork in soil with hydraulic excavator of 0.90 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to embankment location and complete as per specifications.	Cum	90.00	Rupees Ninety Only
16	328.72	Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of modified proctors density.	Cum	362.00	Rupees Three Hundred Sixty Two Only

nature of the contractor

Executive Engineer
RRNagara Division
BBMP